

EMMERGENCY REHEBILITAION FOR CEEL DAAHIR BOREHOLE**BOQ FOR BOREHOLE REHEBILITAION****DEPTH : 180 M****SWL : 120 M****PUMP WATER LEVEL : 120 M**

NO	Description	UNIT	Qty	Unit Price (USD)	Total Cost (USD)
1	Mobilization of the Crane to the Site	ITEM	1	800	\$ 800
2	Remove existing GI Pipes class " C" After supply and installation new Galvanized Iron class "C" with all necessary fittings	PCS	20	50	\$ 1,000
3	Replace existing Submersible ,After supply brand new LOWARA Submersible pump of 7.5 KW	LS	1	2650	\$ 2,650
4	Supply Control Panel of 7.5 KW	LS	1	200	\$ 200
5	Subtotal Cost				\$ 4,650

EMMERGENCY REHEBILITAION FOR SARMAANYO BOREHOLE ONE**BOQ FOR BOREHOLE REHEBILITAION****DEPTH : 350 M****SWL : 250 M****PUMP WATER LEVEL : 300 M**

NO	Description	UNIT	Qty	Unit Price (USD)	Total Cost (USD)
1	Mobilization of the Crane to the Site	LM	1	800	\$ 800
2	Remove existing GI Pipes class " C" After supply new Galvanized Iron class "C" with all necessary fittings	PCS	50	50	\$ 2,500
3	Replace existing Submersible Pump ,After supply brand new LOWARA Submersible pump of 15 KW	LS	1	3800	\$ 3,800
5	Subtotal Cost				\$ 7,100
5	Grand Total Cost of two Boreholes				\$ 11,750